

Procurement Office 675 West Main Street Rochester, NY 14611 585-697-3625

Fax: 585-697-7164 www.rochesterhousing.org

March 6, 2013

To: Contractors

RE: Rochester Housing Authority,

**Scattered Sites-Roof Replacements** 

### **ADDENDUM #1**

Please find attached addendum #1 to the above-mentioned Project.

This addendum consists of (3) pages.

See attached

## **Acknowledgement:**

I have received the above referenced Addendum #1, and have used it in the calculation/preparation of this bid.

Contractor

THIS MUST BE SUBMITTED WITH YOUR BID SUBMISSION FAILURE TO DO SO MAY RENDER YOUR BID INVALID.

### Prepared By:

PASSERO ASSOCIATES 100 Liberty Pole Way Rochester, NY 14604

### ADDENDUM NO. 1

# FOR THE ROCHESTER HOUSING AUTHORITY SCATTERED SITE ROOF REPLACEMENT

ΑT

#### 10 SITES

98 FILMORE, 244 LINCOLN AVE., 160 MERRIMAN STREET, 18 ALEXANDER STREET, 16 GLASSER STREET, 39-41 DELMAR STREET, 217 DAKOTA STREET, 289 ROSLYN STREET, 37 IROQUOIS STREET, 25-29 NORRIS DRIVE

### Items to be included in Project

Contract bidders of record for the subject project are hereby informed that this Addendum forms a part of the contract and will be amended as contained below and as attached or indicated herein. Receipt of the Addendum shall be acknowledged on the Proposal Form.

These changes are to be incorporated into the Construction Documents and shall apply to the Work with the same meaning and force as if they had been included in the original documents. Wherever this Addendum modifies a portion of a paragraph of the Project Manual, or portion of any Drawings, the remainder of the paragraph or Drawing shall remain in force.

### **ITEMS ADDED TO CONRACT DOCUMENTS:**

1. Sk-1, This detail reflects the work associated with the chimney caps, this applies to all addresses that have a chimney.

**END OF ADDENDUM #1** 



Chimney Crown

Rochester Housing Authority 675 West Main Street Rochester, Ny 14611

Project No. 20060117.0036

EXISTING BRICK, REPAIR/REPOINT AS REQUIRED A MIN. THICKNESS OF 2"
(TAPERED AWAY FROM FLUE) **METAL FLASHING** DRIP EDGE BACKER ROD AND SEALANT, TYPICAL AT FLUE PIPE EXTEND FLUE PIPE 8" MIN.
ABOVE NEW CONCRETE
CROWN (FLUE PIPE
EXTENSION TO MATCH
EXISTING FLUE PIPE
MATERIAL) METAL FLUE CAP WITH SCREEN PROVIDE ANCHOR

Chimney Crown Detail 3/4" = 1'-0"

PASSERO ASSOCIATES engineering architecture

UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS

Passero Associates