



Procurement Office
675 West Main Street
Rochester, NY 14611
585-697-3625
Fax: 585-697-7164
WWW.ROCHESTERHOUSING.ORG

May 3, 2013

To: Contractors

RE: Rochester Housing Authority,
Electric Meter Upgrades Holland Townhouse Project

ADDENDUM #1

Please find attached addendum #1 to the above-mentioned Project.

This addendum consists of **(3) pages including cover**

SEE ATTACHED

Acknowledgement:

I have received the above referenced Addendum #1, and have used it in the calculation/preparation of this bid.

Contractor

**THIS MUST BE SUBMITTED WITH YOUR BID SUBMISSION
FAILURE TO DO SO MAY RENDER YOUR BID INVALID.**

**Rochester Housing Authority
Holland Townhouses Electric Meter Upgrades
HUNT 2285-004**

ADDENDUM NO. 1

May 3, 2013

The following Addendum (Addenda) shall be considered a part of the contract documents prepared by HUNT ENGINEERS, ARCHITECTS & LAND SURVEYORS; P.C. dated March 29, 2013.

Project Manual Sections Issued by this Addendum:

None

Drawings Issued by this Addendum:

None

Revisions to Project Manual:

ITEM AD 1-1 Refer to Section "01 50 00 – Temporary Facilities and Controls"

Add paragraph 3.3, C to read: "Water – Water is not available on-site. Contractor is responsible to provide water necessary for all construction activities."

ITEM AD 1-2 Refer to Section "32 92 19 – Seeding"

Amend paragraph 3.5, A to read: "Provide maintenance at no extra cost to Owner. Contractor to provide water required for maintenance as water is not available on-site."

Revisions to Drawings:

ITEM AD 1-3 Refer to Drawing "E1.1 – Photo/Meter Key Plan & Notes"

Under the Section Heading "General Notes"

Revise note "J" to include: "RG&E recommends disconnecting of power by 8:00 am and energizing power by 1:00 pm in order to ensure power is restored by the end of the work day."

Add note "L" to read: "Contractor to coordinate with RG&E and the City of Rochester Inspector a minimum of 72 hours prior to any required power outages, energizing power, or other items requiring coordination."

Add note "M" to read: "Grounding in meter boxes is not permitted."

Add note "N" to read: "Contractor to provide RG&E standard Type 2 or 3-meter setup depending on location. If any meter location does not allow for the required space to mount a standard 2 or 3-meter setup, the contractor shall provide a multi-meter gangway setup."

Add note "O" to read: "Contractor to coordinate with RG&E for any work required in the proposed RG&E hand holes, including providing pipe as necessary for RG&E to make hand hole connection, the pulling of lines, and the connection of the services in the hand hole."

ITEM AD 1-4 Refer to Drawing "E1.1 – Photo/Meter Key Plan & Notes"

Under the Section Heading "General Site Notes"

Add note "QQ" to read: "Contractor to demarcate all existing on-site electric lines (such as site lighting) utilizing qualified personnel or subcontractors such as On-the-Mark or Premier. Contractor shall have a licensed surveyor field locate the corners of all buildings, the existing demarcated electric lines, and the as-built electric lines installed under this contract. The Contractor shall provide to the Client three full scale paper copies (maximum 1"=50' scale) and an AutoCAD DWG format (version 2011 or earlier)."

Add note "RR" to read: "Contractor is responsible for seeding and restoration of areas that are within the defined scope of work. Areas disturbed by RG&E or their contractor will be seeded and restored by RG&E or their contractor."

**Rochester Housing Authority
Holland Townhouses Electric Meter Upgrades
HUNT 2285-004
ADDENDUM NO. 1**

Page 2

ITEM AD 1-5 Refer to Drawing "E1.1 – Photo/Meter Key Plan & Notes"

Under the Section Heading "Construction Notes"

Revise note 7 to include: "Contractor shall relocate any electrical equipment/devices that interfere with the new house panel installation."

**ITEM AD 1-6 Refer to Drawings "E1.1 – Photo/Meter Key Plan & Notes" and "E1.2 – 2 Meter Unit:
Exg. Cond. & Details"**

Remove from the contract the replacement of meter location #3 (also Photo #3) on Building 15 for Apartments 246 and 250. Meter and service lateral to remain for this location.

End of Addendum No. 1