



Procurement Department  
675 West Main Street  
Rochester, NY 14611  
585-697-6182  
procurementRHA@rochesterhousing.org

### IFB110373 Roof Replacements (R11) Scattered Sites

#### ADDENDUM NO. 1

June 23, 2016

The following Addendum (Addenda) shall be considered a part of the contract documents prepared by Hunt Engineers, Architects & Land Surveyors, P.C. dated March 31, 2016

#### APPENDIX 2 – ROOF PLANS AND ELEVATIONS

##### Drawing Revisions:

- AD1 - 1 Drawing A3 “ROOF PLAN”; ADD note: “At Hot Vents (H.V.), Provide flashing per Reference Note 9/A0.3.”
- AD1 - 2 Drawing A3.3 “EXTERIOR PHOTOS”; At NW Photo, DELETE note referencing Hot Vent, and ADD note: “Hot Vent shall be removed and replaced in new location by Owner, including cutting new opening in roof sheathing. (New Hot Vent location shall be clear of adjacent Main Roof edge: 1 foot minimum horizontally and shall extend vertically a minimum of 2 feet higher than the ridge of the adjacent roof).

Contractor shall remove existing flashing, patch existing opening and provide new flashing for Hot Pipe as described in Reference Note 9/A0.3. Contractor shall coordinate this work with Owner – the Rochester Housing Authority at start of tear-off and re-roofing operations.”

##### Acknowledgement:

I have received this Addendum # 1 and have used it in the calculation/preparation of this bid.

\_\_\_\_\_ Contractor

This must be submitted with your bid submission  
or your bid may be rendered invalid.

