



**Procurement Office**  
675 West Main Street  
Rochester, NY 14611  
585-697-3625  
Fax: 585-697-7164  
[WWW.ROCHESTERHOUSING.ORG](http://WWW.ROCHESTERHOUSING.ORG)

June 16, 2015

To: Potential Bidders

RE: Rochester Housing Authority,  
**Asbestos Abatement-33 Kestrel Street**

*3 pages including cover*

**ADDENDUM #1**

**See Attached**

**Acknowledgement:**

**I have received the above referenced Addendum # 1 and have used it in the calculation/preparation of this bid.**

\_\_\_\_\_  
Contractor

**THIS MUST BE SUBMITTED WITH YOUR BID SUBMISSION**  
**FAILURE TO DO SO MAY RENDER YOUR BID INVALID.**

**TO ALL BIDDERS:**

TO ALL BIDDERS:

The following constitutes ADDENDUM NO. 1 of the Contract Documents. Each Bidder shall acknowledge receipt of the Addendum.

Pages ADD 1-1 and ADD1-2 constitutes Addendum No. 1 to the Contract Documents. This addendum contains changes to the requirements of the Bidding Documents, Technical specifications and Construction Drawings which have been issued to date. Such changes are to be incorporated into the Construction documents and shall apply to the Work with the same meaning and force as if they had been included in the original documents. Wherever this Addendum modified a portion of a paragraph of the Project Manual, or portion of any Drawings, the remainder of the paragraph or Drawing shall remain in force. Make the following changes to the Contract Drawings, Contract Specifications and Related Documents:

**CONTRACT SPECIFICATIONS**

**SPECIFICATION SECTION 028200 – ASBESTOS REMEDIATION**

1-1) ADD to Paragraph 1.02B the following:

“Electric baseboard heaters shall be carefully disconnected, cleaned and turned over to RHA. They shall be left in the apartment when the work is complete.”

1-2) DELETE the last sentence of Paragraph 1.02C and ADD to Paragraph 1.02C the following:


“The main disconnect for Unit 33 is outside the building adjacent to Unit 31. It can be tapped for power during abatement work. RHA will complete the connection of the contractor’s sub-panel. The Contractor shall coordinate with RHA and meet RHA Electricians on-site a minimum of one week prior to the start of abatement work. The Contractor shall provide any necessary connectors or knock out filters.”

1-3) ADD to Paragraph 1.02F the following:

“There is an outside water source available at the building for Contractor use.”

1-4) ADD Paragraph 1.02G to read as follows:

“The Contractor will be allowed to use the parking space in front of the unit for a dumpster. The Contractor shall protect RHA property from damage.”



**CONTRACT DRAWINGS**

DRAWING AR-1: ASBESTOS REMOVAL – GROUND FLOOR PLAN

1-5) ADD Specific Note 4 and ADD to the patio door area to read as follows:

“4. Remove door frame as necessary to access door caulk.”

END OF ADDENDUM NO. 1