

SECTION 003126 – EXISTING HAZARDOUS MATERIALS INFORMATION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

Existing Hazardous Materials reports are included as attachments at the end of this section and are hereby incorporated into the Procurement and Contracting Requirements by reference.

A copy of LaBella Associates, D.P.C., "Limited Pre-Renovation Regulated Building Materials Inspection" report dated August 24, 2023, is bound in this Project Manual (Attachment A).

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 003126



ATTACHMENT A:
LIMITED PRE-RENOVATION
REGULATED BUILDING MATERIALS
INSPECTION REPORT -
AUGUST 24, 2023

Limited Pre-Renovation Regulated Building Materials Inspection

Location:

26 Weld Street
Rochester, New York 14605

Prepared for:

Rochester Housing Authority
675 West Main Street
Rochester, New York 14611

LaBella Project No.

2232834

August 24, 2023



Table of Contents

1.0	PROJECT DESCRIPTION	1
2.0	INSPECTION PROCEDURES	1
3.0	INSPECTION LIMITATIONS	1
4.0	INSPECTION RESULTS	2
4.1	Asbestos-Containing Materials (ACMs)	2
4.2	PCB-Containing Materials and Equipment.....	2
4.3	Mercury-Containing Equipment (MCE).....	2
4.4	Lead – Based Paint (LBP).....	3
5.0	OBSERVATIONS AND CAUTIONARY STATEMENTS	3

Appendices

Asbestos Bulk Sample Summary Table	T-1
Appendix A – Inspection Fact Sheet	FS-1
Appendix B – Sample Location Drawings	
Appendix C – Inspection Photos	
Appendix D – Laboratory Analytical Reports	
Appendix E – Licenses and Certifications	



1.0 PROJECT DESCRIPTION

In accordance with current regulations, LaBella Associates, D.P.C. (LaBella) conducted a Limited Pre-Renovation Regulated Building Materials (RBM) Inspection of the residential unit located at 26 Weld Street in Rochester, New York. The objective was to identify suspect RBMs, such as Asbestos-Containing Materials (ACM), Lead-Based Paint (LBP), PCB-containing materials and equipment and Mercury-containing equipment (MCE) that may require abatement or removal prior to or during renovation activities due to applicable regulations.

The areas inspected were limited to the following locations:

- Interior wall systems
- Interior ceiling systems
- Attic crawlspace

Materials and locations understood to be impacted by this project were determined from information provided by Rochester Housing Authority.

2.0 INSPECTION PROCEDURES

The following procedures were used to obtain the data for this Report:

- A. Existing documentation was requested for review. No record drawings or documentation of previously completed inspections were made available.
- B. A visual inspection of the limited areas referenced above was conducted to identify visible and accessible sources of suspect RBMs. Photographs captured during this inspection are attached in Appendix C.
- C. Bulk samples of accessible suspect materials were collected and submitted for laboratory analysis.
- D. Asbestos samples were submitted for laboratory analysis. Preliminary Polarized Light Microscopy analyses were performed by LaBella Laboratories, a NYSDOH accredited laboratory, to determine the presence and percentage of asbestos in each sample. Transmission electron microscopy analyses of NOB materials, if necessary, were performed by AMA Laboratories.
- E. Suspect painted or glazed materials were spot checked in the field using X-Ray Fluorescence (XRF) testing procedures for the presence of lead.
- F. Results of the laboratory analyses, field testing and the visual on-site inspection were compiled and summarized.

3.0 INSPECTION LIMITATIONS

This inspection was conducted in accordance with generally accepted environmental engineering practices for this region. Collection of bulk samples of suspect RBMs was limited to those materials readily accessible using hand tools or hand-held power tools. Homogeneous materials were identified and located based on visual observation from readily accessible points. The data derived from representative samples of any given homogeneous material represent conditions that apply only at that particular location. Inspection protocol and methodology requires that sample data be used to draw conclusions about the entire homogeneous area, but such conclusions may not necessarily apply to the general Site as a whole.

No sub-surface investigations were performed to determine the possible presence of regulated materials on or in the immediate vicinity of the Site. No record drawings of the building were available for review as part of this investigation.



LaBella makes no other warranty or representation, either expressed or implied, nor is one intended to be included as part of its services, proposals, contracts, or reports. No inspection can wholly eliminate the uncertainty regarding the potential for undiscovered RBMs. The Work performed by LaBella is intended to reduce, but not eliminate, uncertainty regarding the potential for RBMs at the Site. This inspection report is not intended to be a bid document for an abatement scope of work. This report is intended to satisfy the requirements of NYS Code Rule 56-5 for inspections.

4.0 INSPECTION RESULTS

4.1 Asbestos-Containing Materials (ACMs)

Based on laboratory analyses of bulk samples collected, the following materials were determined to contain greater than 1% asbestos. However, the following table does not include all of the materials sampled during this inspection; for a full list of materials sampled see the *Asbestos Bulk Sample Summary Table* immediately following this report.

Type of Material	Typical Location	Estimated Amount ¹	Friability	Condition
White Joint Compound	See Description Below	3,850 SF	Non-Friable*	Good
White Stucco	See Description Below	225 SF	Non-Friable*	Good

*This material is considered to be non-friable in its current, intact condition. However, this material has the potential to become friable during any renovation/demolition activities that will disturb the material.

ACM Project Specific Details

Joint Compound

White asbestos-containing joint compound is located on the walls and ceilings in the following locations:

- Kitchen
- Living/Dining Room
- Laundry Room
- Entry/Stairwell
- Bedroom 1
- Bedroom 2
- Bedroom 3
- Bathroom
- Hallway

Stucco

White asbestos-containing stucco is located on the ceiling in the following locations:

- Kitchen
- Bedroom 1
- Hallway

4.2 PCB-Containing Materials and Equipment

No suspect PCB-containing materials or equipment impacted by the project scope were observed during the site inspection.

4.3 Mercury-Containing Equipment (MCE)

No suspect mercury-containing equipment impacted by the project scope were observed during the site inspection.

¹ For general reference only: Quantities reflect only those materials understood to be impacted by the project. Estimated amounts of confirmed ACM listed above were obtained through field observations made during site visits. Quantities are approximations and LaBella assumes no responsibility if used for bidding.



4.4 **Lead – Based Paint (LBP)**

Several representative interior painted and glazed surfaces were observed and tested for the presence of lead-based paint using XRF testing procedures. In accordance with Environmental Protection Agency (EPA) protocols, none of the tested surfaces were determined to contain lead above the action level threshold of 1.0 mg/cm². However, additional lead-based materials may exist within the building. Therefore, Contractors shall be responsible for determining the quantity, location and condition of materials not tested during this inspection.

The building and spaces inspected for this project do include residential spaces applicable to the requirements of EPA lead-based paint management regulations. Therefore, EPA 40 Code of Federal Regulations (CFR) 745: Lead-Based Paint Renovation, Repair and Painting (RRP) Program Rule requirements do apply. Additionally, lead was detected at low concentrations in a variety of building materials (i.e., door components, ceilings, wall base, etc.). Renovation and demolition contractors should be informed of the presence of lead for OSHA compliance considerations.

For purposes of reading this report, and understanding which wall or component in a particular space was sampled, walls were assigned the letters A, B, C, or D. The wall labeled as “A” is the address side of the building; walls B, C, and D will follow clockwise in succession.

5.0 **OBSERVATIONS AND CAUTIONARY STATEMENTS**

Vermiculite

Vermiculite has been used as loose insulation in attics, walls, CMU block, and as a component of plaster, fireproofing and other building materials. The NYS Department of Health considers loose-fill Vermiculite to be an asbestos-containing material, and that building materials containing Vermiculite should be treated as asbestos-containing until sent for additional analysis and proven negative in accordance with NYS DOH guidelines.

Vermiculite was **not** observed in spaces and materials inspected for this project. However, destructive investigation of wall cavities was not conducted, and therefore the presence or extent of this material's application throughout the building was not determined. Cautionary measures should be taken during construction, renovation, and demolition to ensure that proper steps are taken if Vermiculite is discovered in previously inaccessible locations. If Vermiculite is discovered, work should be stopped immediately to address the issue and prevent the uncontrolled release and distribution of an asbestos-containing material.

Potentially Hidden/Inaccessible RBMs

Although this inspection was conducted in a manner consistent with recognized professional practices, the potential does exist for additional RBMs to be located in the following inaccessible areas because of the operational constraints mentioned above:

- Behind sheetrock surfaces
- On floor surfaces potentially covered by multiple layers of building materials such as, plywood, floor tile, etc.
- Inside wall and/or ceiling cavities
- Exterior of the building
- Electrical components

If future building renovations are to take place, it is recommended that the above areas/materials be re-investigated using destructive sampling techniques, as necessary, in order to identify and sample currently hidden/inaccessible suspect RBMs that could potentially be discovered during building renovations.

Asbestos Bulk Sample Summary Table

Asbestos Bulk Sample Summary Table

Limited Pre-Renovation Regulated Building Materials Inspection
26 Weld Street
Rochester, New York 14605

Items in Bold are Confirmed ACM

<i>Sample #</i>	<i>Type of Material</i>	<i>Sample Location</i>	<i>Results % Asbestos</i>
1A	Gray Drywall	Bedroom 1, Wall	None Detected
1B	Gray Drywall	Closet, Ceiling	None Detected
2A	White Joint Compound	Living/Dining Room, Wall	None Detected
2B	White Joint Compound	Kitchen, Wall	Chrysotile 2.8%
2C	White Joint Compound	Kitchen, Wall	Chrysotile 2.7%
2D	White Joint Compound	Living/Dining Room, Ceiling	None Detected
2E	White Joint Compound	Bedroom 3, Ceiling	Chrysotile 2.3%
2F	White Joint Compound	Bedroom 3, Wall	Chrysotile 2.9%
2G	White Joint Compound	Hallway, Wall	Chrysotile 1.8%
2H	White Joint Compound	Bathroom, Wall	Chrysotile 1.7%
2I	White Joint Compound	Bedroom 2, Wall	Chrysotile 2.2%
3A	Tan Cove Molding Mastic	Kitchen, Wall Base	None Detected
3B	Tan Cove Molding Mastic	Bedroom 1, Wall Base	None Detected
4A	White Stucco	Kitchen, Ceiling	Chrysotile 1.7%
4B	White Stucco	Hallway, Ceiling	Chrysotile 1.5%
4C	White Stucco	Bedroom 1, Ceiling	Chrysotile 1.8%
5A	Brown Blown-In Insulation	Attic Crawlspace, On Top of Drywall Ceilings	None Detected
5B	Brown Blown-In Insulation	Attic Crawlspace, On Top of Drywall Ceilings	None Detected
5C	Brown Blown-In Insulation	Attic Crawlspace, On Top of Drywall Ceilings	None Detected



APPENDIX A:

INSPECTION FACT SHEET

Inspection Fact Sheet

Name and Address of Building/Structure

26 Weld Street

Rochester, New York 14605

Name and Address of Building/Structure Owner

Rochester Housing Authority

675 West Main Street

Rochester, New York 14611

Name and Address of Owner's Agent

LaBella Associates, D.P.C.

300 State Street, Suite 201

Rochester, New York 14614

Name of the Firm & Person Conducting the Inspection

LaBella Associates, D.P.C.

Chris Enright (NYSDOL Cert. #06-08603)

Cory Stamp (LBP-R-22573-2)

Date the Inspection Was Conducted

July 26, 2023



APPENDIX B:

SAMPLE LOCATION DRAWINGS

NOT FOR CONSTRUCTION

It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2023 LaBella Associates

HAZARDOUS MATERIAL
INSPECTION
26 WELD ST
ROCHESTER, NY 14605

NO.	DATE:	DESCRIPTION:
Revisions		
PROJECT NUMBER:		
2232834		
DRAWN BY:		
CJS		
REVIEWED BY:		
CRE		
ISSUED FOR:		
SAMPLE LOCATIONS		
DATE:		
AUGUST 2023		
DRAWING NAME:		


SAMPLE LOCATION MAP

DRAWING NUMBER:

H101

C

ITEMS IN BOLD ARE **CONFIRMED ACM**





APPENDIX C:

INSPECTION PHOTOS




Photo 1

View of White Asbestos-Containing Joint Compound on Walls & Ceiling in the Kitchen



Photo 2

View of White Asbestos-Containing Joint Compound on Walls & Ceiling in the Bedroom 3



Photo 3

View of White Asbestos-Containing Joint Compound on Walls & Ceiling in the Bathroom



Photo 4

View of White Asbestos-Containing Stucco on the Ceiling in the Kitchen




Photo 5

View of White Asbestos-Containing Stucco on the Ceiling in the Hallway



Photo 6

View of White Asbestos-Containing Stucco on the Ceiling in Bedroom 1



APPENDIX D:
LABORATORY ANALYTICAL
REPORTS

Bulk Sample Asbestos Analytical Report

LABELLA ASSOCIATES, DPC
ANALYTICAL LABORATORY
300 STATE STREET
ROCHESTER, NY 14614
585.454.6110 FAX 585.454.3066

LBL ELAP # 11184
All TEM analysis by AMA Lab, ELAP # 10920
PLM Methods: 198.1, 198.4 & 198.6
RSD: 18.3

LBL JOB # 83523

Page 1 of 1

Client Code:

CLIENT: Labella Associates

Project Number: 2232834

ADDRESS: 300 State Street

Rochester, NY 14614

Sample Type: PLM Bulk

Sample Date: 7/26/2023

PROJECT LOCATION: 26 Weld Street, Rochester, NY

Field ID	LBL ID	Method	Asbestos Type	%	Other Fibers	%	Matrix	%	Color/Description
1A	83523-1	P	ND		ND		MIN	100	GRAY DRYWALL
1B	83523-2	P	ND		ND		MIN	100	GRAY DRYWALL
2A	83523-3	P	ND		ND		MIN	100	WHITE JOINT COMPOUND
2B	83523-4	P	CHYRSOTILE	2.8	CELL	0.2	MIN	97	WHITE JOINT COMPOUND
2C	83523-5	P	CHYRSOTILE	2.7	CELL	0.3	MIN	97	WHITE JOINT COMPOUND
2D	83523-6	P	ND		ND		MIN	100	WHITE JOINT COMPOUND
2E	83523-7	P	CHYRSOTILE	2.3	CELL	0.7	MIN	97	WHITE JOINT COMPOUND
2F	83523-8	P	CHYRSOTILE	2.9	CELL	0.1	MIN	97	WHITE JOINT COMPOUND
2G	83523-9	P	CHYRSOTILE	1.8	CELL	0.2	MIN	98	WHITE JOINT COMPOUND
2H	83523-10	P	CHYRSOTILE	1.7	CELL	0.3	MIN	98	WHITE JOINT COMPOUND
2I	83523-11	P	CHYRSOTILE	2.2	CELL	0.8	MIN	97	WHITE JOINT COMPOUND
3A	83523-12	T	ND		ND		MIN/BINDER	100	TAN MASTIC
3B	83523-13	T	ND		ND		MIN/BINDER	100	TAN MASTIC
4A	83523-14	P	CHYRSOTILE	1.7	CELL	0.3	MIN	98	WHITE STUCCO
4B	83523-15	P	CHYRSOTILE	1.5	CELL	0.5	MIN	98	WHITE STUCCO
4C	83523-16	P	CHYRSOTILE	1.8	CELL	0.2	MIN	98	WHITE STUCCO
5A	83523-17	P	ND		CELL	100	ND		BROWN BLOWN-IN INSULATION
5B	83523-18	P	ND		CELL	100	ND		BROWN BLOWN-IN INSULATION
5C	83523-19	P	ND		CELL	100	ND		BROWN BLOWN-IN INSULATION

LAB DIRECTOR: Matthew Smith

Date: 7/26/23

Method Code: P - Friable PLM result N - NOB PLM result T - TEM result IN* - Inconclusive G - Gravimetric Matrix Reduction where sample residue weight is less than 1% of original sample weight, TEM not required.

Terms: ND** - None Detected CELL - Cellulose JC - Joint Compound MIN - Mineral GLASS - Fiberglass <1** - Trace PLAS - Plaster Vermiculite - Vermiculite is reported as an asbestos-containing mineral in accordance with NYSDOH determinations and requirements. See NYSDOH guidance, available upon request.

* "Polarized-light microscopy (PLM) is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can be used to determine if this material can be considered to be non-asbestos containing."

** Please note: Due to interference from sample matrix components results reported via PLM method ELAP 198.1 as negative (ND) or less than 1% (Trace) may be inaccurate and reported as a False Negative. It is recommended that additional analytical techniques such as gravimetric reduction, TEM and others be used to reduce obscuring effects of some matrix components yielding more accurate results.

**ASBESTOS SAMPLING SURVEY
BULK SAMPLE LOG
AND CHAIN OF CUSTODY**

Location: 26 Weld Street, Rochester NY

Client: Rochester Housing Authority

Job No.: 2232834

Rates: Standard

Date: 7/26/2023

Relinquished by: Chris Enright

Sampled By: Chris Enright

Received by: Matt Smith 7/26/23

LaBella Lab No.: 83523

Number of Samples: _____

STOP Positive: (YES) NO

P 1
P 2
- P 3
+ P 4
+ P 5
- P 6
+ P 7
+ P 8
+ P 9
+ P 10
+ P 11
T 12
T 13
+ P 14
+ P 15
+ P 16
P 17
P 18
P 19

Field ID #	Sample Location	Type of Suspect ACM to be Analyzed	Approx. Amount
1A	Bedroom 1, Wall	Gray Drywall	
1B	Closet, Ceiling	Gray Drywall	
2A	Living Room/Dining Room, Wall	White Joint Compound	
2B	Kitchen, Wall	White Joint Compound	
2C	Kitchen, Wall	White Joint Compound	
2D	Living Room/Dining Room, Ceiling	White Joint Compound	
2E	Bedroom 3, Ceiling	White Joint Compound	
2F	Bedroom 3, Wall	White Joint Compound	
2G	Hallway, Wall	White Joint Compound	
2H	Bathroom, Wall	White Joint Compound	
2I	Bedroom 2, Ceiling	White Joint Compound	
3A	Kitchen, Wall Base	Tan Cove Molding	
		Mastic	
3B	Bedroom 1, Wall Base	Tan Cove Molding	
		Mastic	
4A	Kitchen, Ceiling	White Stucco	
4B	Hallway, Ceiling	White Stucco	
4C	Bedroom 1, Ceiling	White Stucco	
5A	Attic Crawlspace, On Top of Drywall	Brown Blown In Insulation	
5B	Attic Crawlspace, On Top of Drywall	Brown Blown In Insulation	
5C	Attic Crawlspace, On Top of Drywall	Brown Blown In Insulation	

XRF Lead Sampling Summary Table
26 Weld Street
Rochester, New York 14605
LaBella Project No. 2232834

Reading No.	Location (Room)	Wall (A, B, C D) & Structure	Substrate	Color	XRF Result
1	Calibration Check	----	----	----	PASS
2	Calibration Check	----	----	----	PASS
3	Calibration Check	----	----	----	PASS
4	Calibration Check	----	----	----	PASS
5	Calibration Check	----	----	----	PASS
6	Calibration Check	----	----	----	PASS
7	Living Room	A	Drywall	White	0.0
8	Living Room	A, Wall Base	Vinyl	Brown	0.2
9	Living Room	D, Window Sill	Wood	White	0.0
10	Living Room	C, Column	Wood	White	0.1
11	Living Room	A, Door	Wood	Green	0.1
12	Living Room	A, Chair Rail	Wood	White	0.0
13	Laundry Room	A, Window Sill	Wood	White	0.0
14	Laundry Room	D	Drywall	White	0.0
15	Kitchen	D	Drywall	White	0.0
16	Kitchen	C, Door	Drywall	Brown	0.0
17	Kitchen	C, Door Case	Wood	White	0.0
18	Kitchen	D, Wall Base	Vinyl	Brown	0.0
19	Stairwell	D, Chair Rail	Wood	White	0.0
20	Stairwell	Stringer	Wood	Brown	0.0
21	Stairwell	Riser	Wood	Brown	0.0
22	Bedroom 1	C	Drywall	White	0.0
23	Bedroom 1	C, Ledge	Wood	White	0.0
24	Bedroom 2	D	Drywall	White	0.0
25	Bedroom 2	D, Ledge	Wood	White	0.0

I = Intact Condition. No visible damage or deterioration

P = Poor Condition. Paint is chipped, peeling, or otherwise damaged

XRF Lead Sampling Summary Table
26 Weld Street
Rochester, New York 14605
LaBella Project No. 2232834

Reading No.	Location (Room)	Wall (A, B, C D) & Structure	Substrate	Color	XRF Result
26	Bedroom 2	D, Trim	Wood	White	0.0
27	Bedroom 2	Ceiling	Drywall	White	0.1
28	Bathroom	C, Rail	Wood	White	0.0
29	Bathroom	C	Drywall	White	0.0
30	Bathroom	C, Wall Base	Vinyl	Brown	0.0
31	Bedroom 3	A	Drywall	White	0.0
32	Bedroom 3	A, Ledge	Wood	White	0.0
33	Bedroom 3	A, Trim	Wood	White	0.0
34	Bedroom 3	Ceiling	Drywall	White	0.0
35	Hallway	Ceiling	Drywall	White	0.0
36	Calibration Check	-----	-----	-----	PASS
37	Calibration Check	-----	-----	-----	PASS
38	Calibration Check	-----	-----	-----	PASS
39	Calibration Check	-----	-----	-----	PASS
40	Calibration Check	-----	-----	-----	PASS
41	Calibration Check	-----	-----	-----	PASS

I = Intact Condition. No visible damage or deterioration

P = Poor Condition. Paint is chipped, peeling, or otherwise damaged



APPENDIX E:

LICENSES AND CERTIFICATIONS

WE ARE YOUR DOL



**Department
of Labor**

DIVISION OF SAFETY & HEALTH LICENSE AND CERTIFICATE UNIT, STATE OFFICE CAMPUS, BLDG. 12, ALBANY, NY 12226

ASBESTOS HANDLING LICENSE

LaBella Associates, D.P.C.
300 State Street, Suite 201, Rochester, NY, 14614

License Number: 29278

License Class: RESTRICTED

Date of Issue: 03/24/2023

Expiration Date: 03/31/2024

Duly Authorized Representative: Greg Senecal

This license has been issued in accordance with applicable provisions of Article 30 of the Labor Law of New York State and of the New York State Codes, Rules and Regulations (12 NYCRR Part 56). It is subject to suspension or revocation for a (1) serious violation of state, federal or local laws with regard to the conduct of an asbestos project, or (2) demonstrated lack of responsibility in the conduct of any job involving asbestos or asbestos material.

This license is valid only for the contractor named above and this license or a photocopy must be prominently displayed at the asbestos project worksite. This license verifies that all persons employed by the licensee on an asbestos project in New York State have been issued an Asbestos Certificate, appropriate for the type of work they perform, by the New York State Department of Labor.

Amy Phillips, Director
For the Commissioner of Labor

EXCELSIOR

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER



Expires 12:01 AM April 01, 2024
Issued April 01, 2022
Revised March 30, 2023

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MR. MATTHEW SMITH
LABELLA ASSOCIATES
300 STATE STREET SUITE 200
ROCHESTER, NY 14614

NY Lab Id No: 11184

*is hereby APPROVED as an Environmental Laboratory for the category
ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved subcategories and/or analytes are listed below:*

Miscellaneous

Asbestos in Friable Material Item 198.1 of Manual
Asbestos in Non-Friable Material-PLM Item 198.6 of Manual (NOB by PLM)

Serial No.: 66308

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at <https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/>, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER



Expires 12:01 AM April 01, 2024
Issued April 01, 2022
Revised March 30, 2023

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MICHAEL GREENBERG
AMA ANALYTICAL SERVICES INC
4475 FORBES BLVD
LANHAM, MD 20706

NY Lab Id No: 10920

is hereby APPROVED as an Environmental Laboratory for the category
ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved subcategories and/or analytes are listed below:

Metals I

Lead, Total EPA 7000B

Miscellaneous

Asbestos in Friable Material Item 198.1 of Manual
EPA 600/M4/82/020
Asbestos in Non-Friable Material-PLM Item 198.6 of Manual (NOB by PLM)
Asbestos in Non-Friable Material-TEM Item 198.4 of Manual
Lead in Dust Wipes EPA 7000B
Lead in Paint EPA 7000B

Sample Preparation Methods

ASTM E-1979-17

Serial No.: 66247

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at <https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/>, by phone (518) 485-5570 or by email to elap@health.ny.gov.

United States Environmental Protection Agency

This is to certify that

LaBella Associates, D.P.C.

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226

In the Jurisdiction of:

All EPA Administered Lead-based Paint Activities Program States, Tribes and Territories

This certification is valid from the date of issuance and expires September 26, 2024

LBP-2226-2

Certification #

August 24, 2021

Issued On



Michelle Price, Chief

Lead, Heavy Metals, and Inorganics Branch

United States Environmental Protection Agency

This is to certify that



Chris Enright

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226 as:

Risk Assessor

In the Jurisdiction of:

All EPA Administered Lead-based Paint Activities Program States, Tribes and Territories

This certification is valid from the date of issuance and expires October 24, 2025

LBP-R-22573-2

Certification #

August 02, 2022

Issued On



Ben Conetta, Chief

Chemicals and Multimedia Programs Branch

